

STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

No. SIA/MH/MIS/59859/2021
Environment & Climate
Change Department
Room No. 217, 2nd Floor,
Mantralaya, Mumbai- 400032.
Date: 13/09/2021

To
M/s.PRL Developers Pvt. Ltd.,
C.T.S. No. 491 A/5, 491 A/6 &
C.T.S No 491 A[pt] & 491 A/4 [pt],
Nahur, Mulund (W), Mumbai.

Subject :Environment Clearance for Amendment & Expansion of Residential Development "Piramal Revanta" at C.T.S. No. 491 A/5, 491 A/6 and C.T.S No 491 A[pt] & 491 A/4 [pt], Nahur, Mulund (W), Mumbai by M/s.PRL Developers Pvt. Ltd.

Reference : Application no. SIA/MH/MIS/59859/2021

This has reference to your communication on the above mentioned subject. The proposal was considered by the SEAC-2 in its 151st meeting under screening category 8 (b) as per EIA Notification, 2006 and recommend to SEIAA. Proposal then considered in 229th Part A meeting of State Level Environment Impact Assessment Authority (SEIAA).

2. Brief Information of the project submitted by you is as below:-

Sr. No.	Description	Details	Unit
1	Plot Area	46,890.20	m ²
2	FSI Area	1,49,946.75	m ²
3	Non FSI Area	1,81,508.44	m ²
4	Total Built-up Area	3,31,455.19	m ²
5	No. of Buildings & Configuration	Sale Tower (Wing A): B+G+34th floors, Height:106.5 m Sale Tower (Wing B): B+G+40th floors, Height:125.10 m Sale Tower (Wing C): B+G+47th floors, Height:149.40 m Sale Tower (Wing D to H): B+G+43th floors, Height:137.00 m Wing J (MLCP): B+G + 11 floors R&R Bldg – 1: B + S + 10th Floors, Height: 32.05 m	-

		R&R Bldg – 2: B + S + 13th Floors, Height: 40.75 m	
		Bldg. IH (Wing I): B + G +11th floor, Height: 34.95m	
6	No. of tenements & Shops	2,766 Flats	Nos.
7	Total Population	12,553	Nos
8	Water requirement	1,700	KLD
9	Sewage generation	1,582	KLD
10	STP Capacity and STP technology	4 STP's of total capacity 1,625 KLD with MBBR technology	KLD
11	STP Location	Basement	-
12	Total solid Waste quantity	Total: 6,277 (Biodegradable: 3766)	kg/day
13	RG Required & Provided	RG required: 10,385.35 RG provided on Ground is 6,629.58 RG provided Podium is 4,428.08 Total RG area - 11,057.66	m ²
14	Power Requirement	Demand Load: 9.2	MW
15	Energy Efficiency	Total Savings: 22.5 By Solar: 4	%
16	No. of DG Set and Capacity	4 x 2000 & 1 x 320 KVA	kVA
17	Parking 4W & 2W	4W: 2,767	Nos.
18	RWH Tank Capacity	10 RWH tanks with 500 KL total capacity	KL
19	Project Cost	Rs. 1,435	Cr.
20	EMP Cost	Capital Cost: Rs. 860 lakh & O&M Cost: 152.2 Lakh/yr	Rs.
21	CER	Not Applicable (as per MoEF&CC OM F. No. 22-65/2017-IA.III dt. 30.09.2020)	-

The major particulars of project as compared to earlier EC are as mentioned below:

Sr. No.	Details	As per Earlier EC (06/11/2018)	Proposed for Amendment/Expansion	Remark
1	Plot Area	33882.20 m ²	46890.0 m ²	Plot area increased by 13,008 m ² by addition of adjacent plot.
	Net Plot	22778.70 m ²	36338.22 m ²	Due to addition of

	Survey No.	491 A/5, 491 A/6		C.T.S. No. 491 A/5, 491 A/6 and C.T.S No 491 A[pt] & 491 A/4 [pt]		C.T.S No 491 A[pt] & 491 A/4 [pt]
2	Total built up area	FSI: 79457.50 m ² Non FSI: 101952.56 m ² Total BUA: 181410.06 m ²		FSI : 149946.75 m ² Non FSI: 181508.44 m ² Total BUA: 331455.19m ²		Increased due to increase in buildable plot as per DCPR 2034
3.	Building Configuration	Sale Tower (Wing A)	B+G+45th floors	Sale Tower (Wing A)	B+G+34th floors	Reduction of 11 floors (B+G+34 floors completed)
		Sale Tower (Wing B)	B+G+45 th floors	Sale Tower (Wing B)	B+G+40 th floors	Reduction of 5 floors (B+G+28 floors completed)
		Sale Tower (Wing C)	B+G+45 th floors	Sale Tower (Wing C)	B+G+47 th floors	Addition of 2 floors (Excavation in progress)
		Sale Tower (Wing D)	B+G+12 th floors	Sale Tower (Wing D)	B+G+43 th floors,	Addition of 31 floors (No work started)
		-	-	Sale Tower (Wing E to H)	B+G+43 th floors	Newly proposed (No work started)
		MLCP	G + 11 floors	Wing J (MLCP)	B+G + 11 floors	Change in outline (part foundation completed)
		-	-	R&R Bldg. - 1	B+S + 10th Floors	Newly proposed (No work started)
3	Building Configuration	-	-	R&R Bldg - 2	B + S + 13th Floors,	Newly proposed (No work started)
		-	-	Bldg IH (Wing I)	B + G +11 th floor,	Newly proposed (No work started)
4	No. of Tenements	981 Flats		2,766 Flats		Increased
5	Population	4,905 Nos.		12,553 Nos.		Increased
6	Water Requirement	687 KLD		1,700 KLD		Increased due to increase in population
7	Sewage Generation	574 KLD		1,582 KLD		
8	STP Capacity	4 STPs of Total capacity 574 KLD		4 STPs of Total capacity 1625 KLD		
9	Solid Waste generation	Total solid waste: 2,453 kg/d Biodegradable: 1,472 kg/d Non-biodegradable: 981 kg/d		Total solid waste: 6,277 kg/d Biodegradable: 3,766 kg/d Non-biodegradable: 2,511 kg/d		

10	RWH details	4 tanks of total capacity 301 m ³	10 tanks of total capacity 500 m ³	Capacity increased
11	RG details	RG area on Ground is 5,698.40 m ² (25.01%); RG area Podium is 5,343 m ² . Total RG area - 11,041.4 m ²	RG provided on Ground is 6,629.58 m ² . RG provided Podium is 4,428.08 m ² . Total RG area - 11,057.66 m ²	Minor Increased
12	DG Sets	3 nos. of 2000 KVA + 1 no. of 415 KVA	4 x 2000 & 1 x 320 KVA	Increased
13	Parking provided	Four Wheeler - 1,346 Nos.	Four Wheeler – 2,834 Nos. Two Wheeler - 224 Nos.	Proposed as per Norms
14	Project Cost	Rs. 494 Cr	Rs. 1,435 Cr	Increased

3. The proposal has been considered by SEIAA in its 229th Part A meeting. SEIAA noted that, PP obtained EC vide No. SEIAA-EC-0000000501 dated 06.11.2018 for plot area of 33882.20 m², FSI Area of 79457.50 m² and Total construction area of 181410.06 m². Now, due to increase in plot area and as per the provision of DCPR, 2034 built up area of project is increased, PP applied for amendment. Proposed total BUA is 331455.19 m². SEIAA decided to accord Environment Clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implantation of following terms and conditions-

Specific Conditions:

A. SEAC Conditions-

1. PP to submit IOD/IOA/Concession Document/Plan Approval or any other form of documents as applicable clarifying its conformity with local planning rules and provisions there under as per the Circular dated 30.01.2014 issued by the Environment Department, Govt. of Maharashtra.
2. PP to obtain and submit following NOCs as per amended plan:
 - a) Civil Aviation
 - b) HRC
 - c) SWD
 - d) Nalla remark
 - d) Revised Tree NOC considering amalgamation of plot.
3. PP to provide aeration tanks of appropriate capacity in all STPs.
4. PP to get NOC from competent authority with reference to Thane creek flamingo sanctuary as the project site falls within 10 Km radius from the said sanctuary boundary.
5. PP to ensure that minimum 25 % four-wheeler and two-wheeler Parking's should be equipped with electric Charging facilities.
6. PP to relocate UGT which are proposed in drive-way.
7. PP to relocate parking shown over the STP.
8. PP to provide Six-meter clear driveway with Nine meter turning radius for continuous fire tender movement around all the buildings.

B. SEIAA Conditions-

1. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
2. PP to provide grass pavers of suitable types & strength to increase the water permeable mother earth area up to 1/3rd of plot area as well as allow effective fire tender movement.
3. PP to achieve at least 5% of total energy requirement from solar/other renewable sources.
4. PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA.III dt.04.01.2019.
5. SEIAA after deliberation decided to grant EC for – FSI- 149915.54 m², Non-FSI- 181539.41 m², Total BUA- 331455.19 m². (Plan approval CHE/ES/1937/T/302, dated 24.02.2021, CHE/ES/1930/T/337(NEW), dated 15.02.2021)

General Conditions:

A) Construction Phase :-

- I. The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. Disposal of muck, Construction spoils, including bituminous material during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in the approved sites with the approval of competent authority.
- III. Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- IV. Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
- V. Arrangement shall be made that waste water and storm water do not get mixed.
- VI. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices.
- VII. The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
- VIII. Permission to draw ground water for construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
- IX. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
- X. The Energy Conservation Building code shall be strictly adhered to.
- XI. All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
- XII. Additional soil for levelling of the proposed site shall be generated within the sites (to

the extent possible) so that natural drainage system of the area is protected and improved.

- XIII. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- XIV. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
- XV. The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
- XVI. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
- XVII. Vehicles hired for transportation of Raw material shall strictly comply the emission norms prescribed by Ministry of Road Transport & Highways Department. The vehicle shall be adequately covered to avoid spillage/leakages.
- XVIII. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
- XIX. Diesel power generating sets proposed as source of backup power for elevators and common area illumination during construction phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel is preferred. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
- XX. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings by a separate environment cell /designated person.

B) Operation phase:-

- I. a) The solid waste generated should be properly collected and segregated. b) Wet waste should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. c) Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
- III. a) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Treated effluent emanating from STP shall be recycled/ reused to the maximum extent

possible. Treatment of 100% grey water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP. b) PP to give 100 % treatment to sewage /Liquid waste and explore the possibility to recycle at least 50 % of water, Local authority should ensure this.

- IV. Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line. No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement.
- V. The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
- VI. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- VII. PP to provide adequate electric charging points for electric vehicles (EVs).
- VIII. Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
- IX. A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
- X. Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes.
- XI. The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at <http://parivesh.nic.in>
- XII. Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1st June & 1st December of each calendar year.
- XIII. A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
- XIV. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO₂, NO_x (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient

location near the main gate of the company in the public domain.


C) General EC Conditions:-

- I. PP has to strictly abide by the conditions stipulated by SEAC& SEIAA.
 - II. If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
 - III. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
 - IV. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
 - V. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
 - VI. No further Expansion or modifications, other than mentioned in the EIA Notification, 2006 and its amendments, shall be carried out without prior approval of the SEIAA. In case of deviations or alterations in the project proposal from those submitted to SEIAA for clearance, a fresh reference shall be made to the SEIAA as applicable to assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.
 - VII. This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.
4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.
5. This Environment Clearance is issued purely from an environment point of view without prejudice to any court cases and all other applicable permissions/ NOCs shall be obtained before starting proposed work at site.
6. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.

7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, amended time to time.

8. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.

9. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1st Floor, D-Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.


Manisha Patankar-Mhaiskar
(Member Secretary, SEIAA)

Copy to:

1. Chairman, SEIAA, Mumbai.
2. Secretary, MoEF & CC, IA- Division MOEF & CC
3. Member Secretary, Maharashtra Pollution Control Board, Mumbai.
4. Regional Office MoEF & CC, Nagpur
5. District Collector, Mumbai Suburban.
6. Commissioner, Municipal Corporation of Greater Mumbai.
7. Regional Officer, Maharashtra Pollution Control Board, Mumbai.

